EXTRA ITEM RATE LIST

Name of Work: Improvements to Roads and Drains at HMT Layout 6th, 7th Block and Surrounding area in Ward No. 14 (Vidyaranyapura).

Name of Agency: M/s. S.S Road Developers, Prop: Sri S.S Mani, No. 2/2, 1st Cross, BSA Road, Fezer Town, Bangalore 560005.

Estimated Cost: 55,00,000.00

Tender Amount : Rs. 40,08,132.57 Lakhs

Work Order No. EE/BTP/WO/156/2022-23 Dated: 10-03-2023.

Sl. No.	Item No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
1	E1	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) **Item No. 5.4, Page No. 9, Vol - II PWD SR 2021-22**	Cum	41.88	5062.99	212038.02	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - II	
2	E2	Providing ruled pointing to cursed stone masonry with lime mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost all materials, labour, usage charges of machinery, curing complete as pre specification. **Item No. 21.10 Page No. 190, Vol - II PWD SR 2021-22**	Sqm	93.42	225.15	21033.51	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - II	

Sl. No.	[redacted] No.	Description of Work	Unit	Qty	Rate	Amount	Whether the items are alternative to items in tender schedule or whether being an additional item	Wheather the extra items s included in the sanctioned Estimate	How the expenditure due to the extra item is proposed to be met out	Whether the item isincluded in the S.R (Referabce if SR to be given . If not Data Should accompany the EIRL	Remarks
3	E3	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite / trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately **Mix 1:3:6 (M10) Using 20 mm nominal size graded crushed coarse aggregate (PWD SR 2021-22 Vol -I Pg 15 item no 2.1.4))**	Cum	8.05	5418.69	43620.45	Additional Item	No	By over all savings in the work	PWD SR 2021-22 Volume - I	
4	E4	Providing and Fixing pre cast Covering Slab 230 mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge	Sqm	32.70	4331.82	141650.51	Additional Item	No	By over all savings in the work	Approved Data Rate	
		Total				**252419.78**					

Percentage Excess $\frac{\textbf{252419.78}}{\textbf{4008132.57}} \times 100 =$ 6.30%

,pproved Tender Amou

Assistant Engineer
New Ward No. 14

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP

Assistant Executive Engineer
Vidyaranyapura Sub Division
B.B.M.P, Bangalore - 97

Executive Engineer
Byatarayanapura Division
BBMP